
Qatar Low-Voltage Busbar Temperature Measurement Procedure



Overview

The test shall be carried out according to IEC 60068-2-2 Test Bb, at a temperature of 70 °C, with natural air circulation, for a duration of 168 h (7 days) and with a recovery of 96 h (4 days).

Key Takeaways

Low-voltage busbar temperature in Qatar should be measured using non-contact infrared sensors, following IEC 61439 thermal limits and KAHRAMAA guidelines for high-ambient conditions.

Regulatory and Design Context

In Qatar, low-voltage switchgear and busbars are governed by IEC 61439-1, which sets the maximum permissible temperature rise for bare copper busbars at 105 K above a 35°C reference ambient, resulting in an absolute busbar temperature limit of 140°C. However, Qatar's summer ambient temperatures can reach 40–50°C, reducing the thermal margin and requiring derating of busbars to prevent overheating and insulation failure.

KAHRAMA



© 2026 CGWEB NETWORK INFRASTRUCTURE - All rights reserved

A evaluates the LV panel up to the vertical busbar, ensuring compliance with local safety and thermal standards. Measurement MethodologyNon-contact infrared (IR) sensors are recommended for busbar temperature monitoring because they provide accurate, instantaneous readings while remaining electrically isolated from live conductors. Key steps include: Sensor Selection and PlacementUse IR sensors suitable for the expected temperature range (-20°C to 1000°C).

Mount sensors at a safe distance from the busbar to avoid electric arcs. For wide busbars, use wide-angle optics (2: 1); for narrow or high-voltage busbars, use narrow optics (20: 1) to maintain measurement accuracy. Paint the busbar surface with a high-emissivity coating to improve IR measurement reliability.

Monitoring Points

Focus on busbar joints and bolted connections, as these are the most susceptible to overheating. Typically, six sensors per switchgear cabinet are used: three on input busbars and three on output busbars.

Data Logging and Alarm Integration

Connect sensors to a central hub (e.g., PM180 touch screen) for real-time display, configuration, and data logging to MicroSD. Integrate with SCADA systems via Modbus TCP for centralized monitoring and alarm management.

Measurement Considerations

Ensure the sensor angle relative to the busbar is appropriate; measurements at 90° yield circular spots, while lower angles produce elliptical spots. Continuous monitoring allows early detection of joint deterioration and prevents thermal overload.

Safety and Operational Notes

Ensure busbars are derated according to ambient temperature and load diversity factors. Verify that connected devices (circuit breakers, terminals) do not have lower temperature limits than the busbar itself. Maintain ambient temperature awareness, as Qatar's hot and humid climate can significantly reduce thermal headroom.

Periodically inspect and recalibrate IR sensors to maintain measurement accuracy. By following this procedure, engineers can ensure safe operation of low-voltage busbars in Qatar, comply with IEC 61439 thermal requirements, and meet KAHRAMAA approval standards while enabling proactive maintenance through continuous temperature monitoring.

© 2026 CGWEB NETWORK INFRASTRUCTURE - All rights reserved

Article Content

IEC 61439 Standards-R1

The test shall be carried out according to IEC 60068-2-2 Test Bb, at a temperature of 70 °C, with natural air circulation, for a duration of 168 h (7 days) and with a recovery of 96 h (4 days). - The UV

Busbar Temperature Monitoring in Switchgear Cabinets

The first symptom of deterioriation is an increase in joint temperature, which can be detected quickly and reliably by continuously monitoring the temperature of each joint using low-cost IR temperature

Busbar Testing Procedure

Discover the essential procedures & best practices for successful busbar testing. Our comprehensive post covers preparation, equipment setup, testing methods, and safety

WIRING CODE 2016

The purpose of these Regulations is to establish standards, principles and guidelines that promote the design, construction, installation, maintenance, operation, energy conservation and metering of safe

IEC 61439 Busbar Standard: A Guide to Low-Voltage Busbar

IEC 61439 is a standard developed by the International Electrotechnical Commission (IEC) that covers design verification for low-voltage electrical products and assemblies. This standard

IEC 61439-1 and IEC 61439-6 Testing Procedure and Key

This three-part webinar series will take a deep dive into IEC 61439-1 and 61439-,6 that defines the service conditions, construction requirements, technical characteristics and verification requirements

Busbar Temperature Measurement (F

To prevent costly downtime and help plan preventative maintenance, it is important that temperatures are continuously monitored. Calex non-contact infrared temperature sensors, in conjunction with a

Switchgear and Busbar Temperature Monitoring

The AP Sensing Linear Heat Detection (LHD) solution consists of a fiber optic sensor cable fitted within the switchgear or attached to the busbar, plus a DTS control instrument that

© 2026 CGWEB NETWORK INFRASTRUCTURE - All rights reserved

Qatar General Electricity & water Corporation

This procedure is prepared and published for all Contractors and Consultants to organize the appropriate activities in order to confirm the method statement for work in the MV and LV network

Detecting Temperature Abnormalities in Bus Ducts Early for More ...

Bus bars that carry large currents cause strong electrical fields around them, making it difficult to measure temperatures with thermocouples or other electrical sensors.

Electricty wiring code 2016 | PDF

This document outlines regulations for low voltage electricity and water installations in Qatar. It establishes standards to promote safe and efficient electrical installations. Key points include: - The

Kahramaa Electrical Wiring Regulations | PDF | Electrical Wiring

The document outlines regulations for electrical installations in Qatar, including definitions of key terms, climatic conditions, and safety requirements. It covers the scope of the regulations, exclusions, and

Thermal Analysis of Busbars from a High Current Power Supply System

An interactive procedure is proposed to predict the busbar operation behavior. Two sets of computational fluid dynamics analysis are presented to calculate the temperature distribution of

Method Statement for Testing & Commissioning Of Enclosed Bus Assemblies

Results to be recorded on the bus duct record sheet. Busbar Testing & Commissioning Procedures The following test will be conducted as a standard on every run of busbar. Insulation

IEC 61439 Compliance for Busbar Systems

The document discusses the IEC 61439 standard for electrical busbar systems. It provides background on the standard and its importance for safety. It explains how the standard helps define

132 kV Busbar Contact Resistance Test: Method Statement

Complete guidance to site inspection and test plan-based 132 kV busbar contact resistance & insulation resistance tests. Test setup, duties, equipment, procedures, & acceptance

Low Voltage Busbar Trunking Guide

© 2026 CGWEB NETWORK INFRASTRUCTURE - All rights reserved

This document provides guidance on low voltage busbar trunking systems according to BS EN 61439-6. It defines busbar trunking systems and components, and describes their typical applications for

Busbar Junction Temperature Measurement in LT Distribution Panel

Objective / Requirement As a part of preventive and predictive maintenance of LT distribution panels in commercial and industrial application, it is also very much essential to measure the temperature of

Contact Us

Continue your research online:

Website: https://cgweb.co.za
Technical inquiry: https://cgweb.co.za/project-enquiry.html

This document is for preliminary research. Verify specifications against current standards, product documentation and project requirements.

© 2026 CGWEB NETWORK INFRASTRUCTURE - All rights reserved